



**North Collier Fire Control and Rescue District
Authority Having Jurisdiction (AHJ) Guidelines for Successful Review or Inspection**

Article Number	FLO 20-02
Effective Date	February 27, 2020
Subject	Water Supply Flow Testing
Objective	Provide Guidance, Requirements and Limitations of Water Supply Flow Testing and Their Results for Building Site Plan and/or Fire Sprinkler Permit Review

BACKGROUND

NFPA 1 requires an adequate water supply to protect facilities, buildings, or portions of buildings constructed; NFPA 13 requires water supply flow testing for fire sprinkler system plans.

POLICY/PROCEDURE

Water supply flow testing according to NFPA 291 shall be conducted solely by North Collier Fire Control and Rescue District (NCFR) personnel and remain valid for a period of six months. Results are provided on NCFR letterhead for inclusion in the permit submittal package and provides measured pressures, calculated gallons per minute (gpm) and extrapolated gpm at 20 psi residual.

CODE REFERENCES

FFPC NFPA 1-18.3; NFPA 13-11.1.5.1, 23.2